

IIMI/Estate/2022/1038

May 25, 2022

Corrigendum: 1


Tender Reference No. : IIMI/Estate/15/2022/105 File No. 353

Tender Title : "Creation of ladies toilet and machine cutting/scraping/polishing of library floors"

The following correction is hereby made in the aforesaid tender:

Clause	Written as in NIT Document	Shall be read as
Last date & time of receipt of tender	Upto 11:00 AM of May 23, 2022	Upto 2:30 PM of May 27, 2022
Date & Time of online opening of technical bid	11:30 AM of May 23, 2022	3:30 PM of May 27, 2022
Financial Bid	Attached at annexure A	Revised financial bid is attached at Annexure B

All other conditions remain unchanged.



Chief Engineer

**Annexure B**

Revised Financial Bid

**Name of Work: Creation of ladies toilet and machine cutting/scrapping/polishing of library floors**

Sl. No	Particular	Unit	Qty	Rate (Incl GST)	Total Amount	Total amount (in words)
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge	Cum	2			
2	Dismantling of urinal/ wash basin of all sizes including disposal of d malba all complete as per directions of Engineer-in-Charge.	each	2			
3	Brickwork with common burnt clay F.P.S non modular brick of class designation 7.5 above plinth level in all shape and size in cement mortar 1:4	Cum	4			
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade. Area of slab up to 0.50 sqm	Sqm	2.4			
5	providing and fixing 1st quality ceramic wall glazed tile over 12 mm thick bed of 1:3 including pointing in white cement with matching pigments	sqmt	44			

6	Supply & Fixing of white rim table top wash basin in circular shape of Hindware/Cera/Jaquar	each	6			
7	Fixing of available Pillar cock with 200 mm extension body (model no. OPP-CHR-15021 PM) SW 60021 of Jaquar make. by cutting hole in stone/slab	each	6			
8	Providing and fixing PTMT angle stop cock 15 mm nominal bore, weighing not less than 85 gms	each	6			
9	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make and as per the direction of Engineer-in-charge	each	4			
10	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	each	2			
11	Providing and fixing ISI marked flush door shutters 30 mm thick conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters:	sqmt	3.78			
12	Anodised Aluminium tower bolt (barrel type) 200x10 mm	each	4			

13	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats (in patches)	Sqm	110			
14	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. complete.	each	2			
15	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500 D or more.	Kg	12			
16	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	Cum	0.07			
17	Rubbing of mossaic flooring to make smooth, free of stain	sqmt	2500			



सिद्धिमूलं प्रबन्धनम्  
भा. प्र. सं. इन्दौर  
IIM INDORE

## भारतीय प्रबंध संस्थान इन्दौर

प्रबंध शिखर, राऊ-पीथमपुर रोड, इन्दौर - 453 556 (म.प्र.), भारत

INDIAN INSTITUTE OF MANAGEMENT INDORE

Prabandh Shikhar, Rau-Pithampur Road, Indore - 453 556 (M.P.), India

18	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	sqm	4			
19	Mirror Light 15x2.5x4.5 inches off white	no.	2			
20	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. 40 mm dia	meter	6			
Total amount Including GST						
Total amount Excluding GST						

Name of firm \_\_\_\_\_

Email Address \_\_\_\_\_

Authorized Person \_\_\_\_\_

Contact Number \_\_\_\_\_

Signature & Seal \_\_\_\_\_