

Dated: January 09, 2018

Name of Work: "Supply, Installation, Testing & Commissioning of VRV/VRF Air-Conditioning System for New Faculty Cabins in J Block (Ground & First Floor) & Split ACs for New Faculty Cabins in Faculty Block-A, B & C at IIM Indore : Interior fitout work - Phase-II"

Ref.: IIMI/Project/01/2018/51 File No.377 (Re-Tender)

Corrigendum: 1


The following amendment have been made in respect of the above referred Notice Inviting e-Tender:

- i) In the Technical Specifications & Bill of material of the Tender Document wherein the item description for indoor units were mentioned, the following corrections are hereby made:

| BOQ Item No. | As is mentioned in the Tender document | Shall be read as |
|--------------|--|---|
| | Item Description | Item Description |
| 2.0 | <p>Indoor Units:</p> <p>Supply, Installation, Testing & Commissioning of Ceiling suspended Cassette type Indoor unit with 4 way / round flow with sensing type, includes washable pre filter, fan section, DX-coil section, inbuilt drain pump, decorative panels etc with interface adaptor kit to communicate with Central Monitoring system, with cordless remote controller complete as per specifications as required.</p> | <p>Indoor Units:</p> <p>Supply, Installation, Testing & Commissioning of Ceiling suspended Cassette type Indoor unit with 4 way / round flow type, includes washable pre filter, fan section, DX-coil section, inbuilt drain pump, decorative panels etc with interface adaptor kit to communicate with Central Monitoring system, with cordless remote controller complete as per specifications as required.</p> |

All other conditions remain unchanged.

Dated: January 09, 2018



(V.P.Thomas)
Chief Engineer